

# Installation instructions


## DB+

### Installation steps



#### 1. Install the membrane

Roll out the membrane and fasten it using staples that are at least 10 mm ( $\frac{3}{8}$ ") wide by 8 mm ( $\frac{5}{16}$ ") long at intervals of 10-15 cm (4"-6") (5-10 cm (2"-4") for blown-in insulation). Install the membrane leaving an additional 4 cm (1 $\frac{1}{2}$ ") overlap at adjacent building structures so that an airtight bond can be applied here subsequently.



#### 2. Overlap the membranes in the case of horizontal installation

Allow the membranes to overlap by approx. 10 cm (4") in the case of installation perpendicular to the supporting structure. The marking that is printed onto the membrane will serve as a guide here.




#### 3. Overlap the membranes in the case of vertical installation

Allow for an overlap of at least 1 cm ( $\frac{1}{16}$ ") on fixed subsurfaces (e.g. rafters) in the case of installation parallel to the supporting structure.



#### 4a. Tape the overlap

Clean the subsurface (dry and free of dust, silicone and grease) and carry out an adhesion test, if necessary. Centre the UNI TAPE system adhesive tape on the overlap and gradually stick it in place, ensuring that there are no folds or tension.




#### 4b. Tape the overlap

Rub firmly using the PRESSFIX application tool to secure the adhesive bond. Ensure that there is sufficient resistance pressure.




#### 5. Sealing to smooth, non-mineral subsurfaces ...

... (e.g. knee walls made of wood-based panels) should also be implemented using UNI TAPE system adhesive tape. Centre the tape and gradually stick it in place, ensuring that there are no folds or tension (PRESSFIX).



### 6. Sealing to rough or mineral substraces

Clean the subsurface. Apply a line of ORCON F adhesive sealant of at least  $d = 5 \text{ mm}$  [ $\frac{3}{16}''$ ], or more in the case of very rough substraces if necessary. Place DB+ onto the adhesive bed, leaving slack to allow for expansion. Do not press the adhesive completely flat.



### 8a. Alternative: Sealing to unplastered substraces

Attach the CONTEGA PV plaster-sealing tape to the wall initially at discrete points using ORCON F. The adhesive strip should be facing inwards.



### 8c. Alternative: Sealing to unplastered substraces

First plaster behind the tape, then apply the tape to the wet plasterwork and plaster over it fully.



### 7. Sealing to unplastered substraces

Guide the vapour control membrane into position. Leave slack for expansion so as to allow for relative motion between components. Remove all release films from CONTEGA SOLIDO SL or CONTEGA SOLIDO IQ. Centre the tape and gradually stick it in place. Rub the tape firmly using the PRESSFIX to secure the adhesive bond. To achieve airtightness, plaster over the masonry and sealing tape.



### 8b. Alternative: Sealing to unplastered substraces


Guide the vapour control membrane into position, remove the release film from CONTEGA PV and stick the vapour control membrane to the tape.



### 9a. Sealing to roughly sawn timber

Clean the subsurface. Apply a line of ORCON F adhesive sealant of at least  $d = 5 \text{ mm}$  [ $\frac{3}{16}''$ ], or more in the case of very rough substraces if necessary. As an alternative, ORCON MULTIBOND adhesive sealant from a roll can be used.






### 9b. Sealing to roughly sawn timber

Place DB+ onto the adhesive bed, leaving slack to allow for expansion. Do not press the adhesive completely flat.



### 10b. Sealing to plastered chimney (insulated or double-shelled)

Then cut into short pieces of TESCON VANA as far as the centre, create corner shapes and then stick in place.



### 12. Corner sealing

Guide TESCON PROTECT pre-folded corner sealing tape into the corner on the release film and stick the first independent adhesive strip. Then remove the release film and stick the second independent adhesive strip.




### 10a. Sealing to plastered chimney (insulated or double-shelled)

Seal DB+ with ORCON F as shown in Figure 6.



### 11. Sealing around pipes and cables

Place a KAFLEX or ROFLEX sealing grommet over the cable or pipe and stick it to DB+. The cable grommets are self-adhesive. Tape the pipe grommets to the membrane using TESCON VANA or UNI TAPE.



### 13. Battens, interior cladding


Install battens (e= max. 65 cm [2' 2"] ) to bear the weight of the insulation, and install interior cladding to provide protection against UV light and other damage.



#### 14. Quality assurance

It is recommended that airtightness should be checked using a BlowerDoor test.

### Roof reburbishment from the outside




#### 1a. Clean the subsurface

Clean the subsurface. Brush off with a hand brush, ...



#### 1b. Clean the subsurface

... if necessary, clean with a vacuum cleaner and wipe down.



#### 2. Preparation

Remove any sharp-edged or pointy objects (e.g. nails) that protrude from the interior cladding into the area between the rafters.



#### 3. If necessary, insert padding

To protect DB+, install panel-shaped insulating material with a strong structure on the existing interior cladding. The thickness of the insulation underneath DB+ should be a max. of  $\frac{1}{3}$  of the total insulation thickness.





#### 4a. Install the membrane

Roll out the membrane parallel to the rafters, align it, allow an extra 3-4 cm (1 1/4" - 1 5/8") at the sides of the rafters and press neatly into the corners with an auxiliary lath.



#### 4b. Install the membrane

Avoid convection tunnels. Install the membrane leaving an additional 4 cm (1 5/8") overlap at adjacent building structures too so that an airtight bond can be applied here subsequently.



#### 5. Fix to the rafters

Fasten the membrane using galvanised staples with a width of at least 10 mm (3/8") and a length of 8 mm (5/16") at intervals of 10-15 cm (4"-6"). The auxiliary lath that can be moved freely can serve as a support for the pneumatic staple gun and protects the membrane against damage.



#### 6a. Clean the subsurface

Clean the subsurface (dry and free of dust, silicone and grease). If necessary, brush off, clean with a vacuum cleaner and wipe down. Very fine dust can be bound by applying TESCON PRIMER.



#### 6b. Seal at the rafters in an airtight manner

Apply a line of ORCON F adhesive sealant of at least  $d = 5 \text{ mm}$  ( $3/16''$ ) to roughly sawn rafters, or more in the case of very rough substrates if necessary, and stick the membrane to this.



#### 7. Sealing to smooth rafters

Bond to smooth/planned rafters using the UNI TAPE universal adhesive tape. Apply the adhesive tape centrally and gradually stick it in place. Rub firmly using the PRESSFIX application tool to secure the adhesive bond. Ensure that there is sufficient resistance pressure. The subsurface must be suitable for permanent sealing. If necessary, brush off, clean with a vacuum cleaner and wipe down. Very fine dust can be bound by applying TESCON PRIMER.



#### 8. Membrane overlaps, if necessary

Allow for an overlap for at least 10 cm (4") between the membranes. Centre the UNI TAPE system adhesive tape on the overlap and gradually stick it in place, ensuring that there are no folds or tension. Rub firmly using the PRESSFIX application tool to secure the adhesive bond. Ensure that there is sufficient resistance pressure.



#### 9. Sealing at the bargeboard

First create a smooth finish on rough wall caps. lean the subsurface. Apply a line of ORCON F adhesive sealant of at least  $d = 5 \text{ mm}$  ( $3/16''$ ), or more in the case of very rough substrates if necessary.






### 10. Sealing at the bargeboard

Place DB+ onto the adhesive bed, leaving slack to allow for expansion. Do not press the adhesive completely flat.



### 11. Sealing at eaves

Sealing to the eaves is carried out analogously to the joint at the bargeboard.



### 12. Sealing around pipes and cables

Place a KAFLEX or ROFLEX sealing grommet over the cable or pipe and stick it to DB+. The cable grommets are self-adhesive.



### 13. Sealing around pipes

Tape the pipe grommets to the membrane using TESCON VANA. Rub firmly using the PRESSFIX application tool to secure the adhesive bond. Ensure that there is sufficient resistance pressure.



### 14. Compartment insulation and underlay

The next step is to insert the insulation and install the underlay, e.g. SOLITEX MENTO 3000. Insulation cover for rafters is possible as an option, but is not required.

## General conditions

pro clima DB+ can be installed with the printed or unprinted side facing the installer, either parallel or at a right angle to the sub-structure, for example, the rafters. It must not be stretched tight.

If installed horizontally (at right angles to the sub-structure) then the maximum space permitted between the rafters is 1 m (3 ft). After laying, it is necessary to support the weight of the insulation with lathing on the inside. The laths should be no more than 65 cm (2' 2") apart. If, when using insulation mats and boards, for example, you expect tension as a result of the insulation weight on the adhesive tape joins, an additional supporting lath should be placed on the overlap. Alternatively, the adhesive tape can be reinforced along the overlap by sticking strips of adhesive tape at right angles to the overlap every 30 cm (1 ft).

Airtight seals can only be achieved on vapour control membranes that have been laid without folds or creases. Ventilate regularly to prevent excessive humidity (e.g. during the construction phase). Occasional rush/inrush ventilation is not adequate to quickly evacuate large amounts of construction-related humidity from the building. Use a dryer if necessary.

To prevent condensation, DB+ should be taped or sealed so that it is airtight immediately after installing the thermal insulation. This particularly applies when working in winter.

### Additional information on blown-in insulation

DB+ can also be used as a membrane for all types of blown-in insulation. Its reinforcement layer prevents tearing during the process of blowing in insulation filling. If installed parallel to the sub-structure, it has the advantage that the overlap is supported on a firm foundation and is therefore protected.

To prevent condensation, the blown-in insulation should be installed immediately after installing the airproofing layer. This particularly applies when working in winter.

---

The information provided here is based on practical experience and the current state of knowledge. We reserve the right to make changes to the recommended designs and processing or to make alterations due to technical developments and associated improvements in the quality of our products. We would be happy to inform you of the current technical state of the art at the time you use our products.

Further information about installation and design details is available in the pro clima planning documentation. If you have any questions, please contact [pro clima Technical Support](<https://proclima.com/service/technical-support>).

### MOLL

**bauökologische Produkte GmbH**

Rheintalstraße 35 - 43

D-68723 Schwetzingen

Fon: +49 (0) 62 02 - 27 82.0

eMail: [info@proclima.de](mailto:info@proclima.de)



---

For over 20 years, Ecological Building Systems has been at the forefront of environmental and sustainable building products supplying a range of innovative airtightness solutions and natural insulations backed up with expert technical support.

**As product suppliers in the UK and Ireland, we're happy to assist you with your projects and have expert technical and sales advice on hand.**



**Call us**

**Great Britain** +44 (0)1228 711511

**Ireland** +353 46 9432104



**Email us**

[info@ecologicalbuildingsystems.com](mailto:info@ecologicalbuildingsystems.com)



**Find us**

**Great Britain** Ecological Building Systems UK Ltd.,  
Cardewlees, Carlisle, Cumbria, CA5 6LF,  
United Kingdom

**Ireland** Ecological Building Systems Ltd.,  
Main Street, Athboy. Co. Meath, C15 Y678,  
Republic of Ireland